

PROJECT NAME ACB Windsor - Clinical Suites: Piping Lengths & Designations			PROJECT NO. 21-515	
CONTRACT DESCRIPTION Contract No.: 11 Contract Name: DSP - Clean Utilities (CU)		REVISION DESCRIPTION Revision No.: Revision Title: Issued For RFP Package		LAST UPDATED (DATE / BY) 2027-02-26 MH

Piping Lengths & Designations					
System	Line Identifier	Piping Spec	Drawing Ref.	Pipe Size [Inch]	CL Length [Ft]
Clean Air	W3461	Ps	20.2-M201	1-1/2"	100
Clean Air	W3462	Ps	20.2-M201	3/4"	70
Clean Air	W3463	Ps	20.2-M201, 20.2-M202	1/2"	18
Clean Air	W3464	Ps	20.2-M201, 20.2-M202	1/2"	12
Clean Air	W3468	Ps	20.2-M201	1/2"	6
Clean Air	W3467	Ps	20.2-M201	1"	14
Oxygen	W6914	Ps	20.3-M201	2"	82
Oxygen	W6915	Ps	20.3-M201, 20.3-M202	3/4"	22
Oxygen	W6917	Ps	20.3-M201	3/4"	19
Oxygen	W6916	Ps	20.3-M201	1"	22
Process Vent	XXXX	Pa	20.4-M202	1"	2
Process Vent	XXXX	Pa	20.4-M202	1-1/2"	1
Process Vent	XXXX	Pa	20.4-M201	3"	36
Process Vent	XXXX	Pa	20.4-M201	2"	38
Process Piping	W6813	Ps	20.5-M201	1"	60

Notes:

1. System "Process Vent" did not include any line identification on the layout drawings.
2. Lengths are based on layout drawings. Contractor to consult Engineer or Client's Rep to coordinate final tie-ins to equipment
3. Contractor to refer to PIDs W34, W69, and W68 for further details.
4. Existing piping for systems is not included in the table above. Items not designated as "New" are considered Out Of Scope for this project.
5. All measurements are taken from centerline based on a 3/8" = 1' scale as noted on the drawings.
6. All clean air lines (instrument air, process air) are added as Clean Air Lines. These systems are provided under the same PID (W34) and contract (20.2)